



**BENCHMARKS:**

Benchmark #1: Big arm of fire hydrant on North side of Valley Court across from #248 West Grand River Avenue (car wash).  
Elevation: 846.85  
Benchmark #2: Big arm of fire hydrant on North side of intersection of Evergreen Avenue and Albert Avenue.  
Elevation: 853.44

**GENERAL NOTES**

1. THE UNDERGROUND STRUCTURES AND UTILITIES SHOWN ON THIS MAP HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORD MAPS, THEY ARE NOT CERTIFIED TO THE ACCURACY OF THEIR LOCATION AND/OR COMPLETENESS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION AND EXTENT OF ALL UNDERGROUND STRUCTURES AND UTILITIES PRIOR TO ANY DIGGING OR CONSTRUCTION ACTIVITIES IN THEIR VICINITY. THE CONTRACTOR SHALL HAVE ALL EXISTING UTILITIES FIELD STAKED BEFORE STARTING WORK.
2. THE CONTRACTOR SHALL PERFORM ALL WORK IN COMPLIANCE WITH TITLE 29 OF FEDERAL REGULATIONS, PART 1926, SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION(OSHA).
3. DRAINAGE ALONG ALL ROADS AND PRIVATE DRIVES SHALL BE KEPT CLEAN OF MUD, DEBRIS ETC. AT ALL TIMES.
4. REFER TO ARCHITECTURAL DRAWINGS FOR PRECISE BUILDING DIMENSIONS.
5. THE CONTRACTOR SHALL CONSULT THE OWNER BEFORE DEVIATING FROM THESE PLANS.
6. IN ALL TRENCH EXCAVATIONS, CONTRACTOR MUST LAY THE TRENCH SIDE SLOPES BACK TO A SAFE SLOPE, USE A TRENCH SHIELD OR PROVIDE SHEETING AND BRACING.
7. ALL EXISTING SURFACE APPURTENANCES (I.E. WATER VALVES, CATCH BASIN FRAMES AND GRATES, MANHOLE COVERS) WITHIN THE PROJECT LIMITS SHALL BE ADJUSTED TO FINISHED GRADE.
8. AREAS DISTURBED OR DAMAGED AS PART OF THIS PROJECTS CONSTRUCTION THAT ARE OUTSIDE OF THE PRIMARY WORK AREA SHALL BE RESTORED, AT THE CONTRACTORS EXPENSE, TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE.
9. THE CONTRACTOR SHALL CALL "MISS DIG" AT 1-800-482-7171 AT LEAST 3 WORKING DAYS (EXCLUDING WEEKENDS AND HOLIDAYS) PRIOR TO CONSTRUCTION.
10. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE CODES, ORDINANCES, DESIGN STANDARDS AND STANDARD SPECIFICATIONS OF THE AGENCIES WHICH HAVE THE RESPONSIBILITY OF REVIEWING PLANS AND SPECIFICATIONS FOR CONSTRUCTION OF ALL ITEMS INCLUDED IN THESE PLANS.
11. UNLESS SPECIFICALLY STATED, THE CONTRACTOR SHALL APPLY FOR AND OBTAIN ALL NECESSARY PERMITS AS REQUIRED FOR CONSTRUCTION OF THIS PROJECT PRIOR TO THE BEGINNING OF WORK FROM THE PREVIOUSLY MENTIONED AGENCIES.
12. THE CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
13. WHEN ANY EXISTING UTILITY REQUIRES ADJUSTMENT OR RELOCATION, THE CONTRACTOR SHALL NOTIFY THE PROPER UTILITY COMPANY AND COORDINATE THE WORK ACCORDINGLY. THERE SHALL BE NO CLAIM MADE BY THE CONTRACTOR FOR ANY COSTS CAUSED BY DELAYS IN CONSTRUCTION DUE TO THE ADJUSTMENT OR RELOCATION OF UTILITIES.
14. THE CONTRACTOR IS TO VERIFY THAT THE PLANS AND SPECIFICATIONS THAT HE/SHE IS BUILDING FROM ARE THE VERY LATEST PLANS AND SPECIFICATIONS THAT HAVE BEEN APPROVED BY ALL APPLICABLE PERMIT-ISSUING AGENCIES AND THE OWNER. ALL ITEMS CONSTRUCTED BY THE CONTRACTOR PRIOR TO RECEIVING THE FINAL APPROVAL AND PERMITS HAVING TO BE ADJUSTED OR RE-DONE, SHALL BE DONE AT THE CONTRACTOR'S EXPENSE.
15. SHOULD THE CONTRACTOR ENCOUNTER CONFLICT BETWEEN THESE PLANS AND SPECIFICATIONS, EITHER AMONG THEMSELVES OR WITH THE REQUIREMENTS OF ANY AND ALL REVIEWING AND PERMIT-ISSUING AGENCIES, HE/SHE SHALL SEEK CLARIFICATION IN WRITING FROM THE OWNER BEFORE COMMENCEMENT OF CONSTRUCTION. FAILURE TO DO SO SHALL BE AT THE SOLE EXPENSE TO THE CONTRACTOR.
16. UNLESS OTHERWISE NOTED THE CONTRACTOR SHALL FURNISH AS-BUILT DRAWINGS INDICATING ALL CHANGES AND DEVIATIONS FROM APPROVED DRAWINGS.
17. ALL SIGNS AND TRAFFIC CONTROL MEASURES DURING CONSTRUCTION AND MAINTENANCE ACTIVITIES SHALL BE CONSTRUCTED AND INSTALLED PER THE LATEST EDITION OF THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (M.M.U.T.C.D.).
18. ALL INFRASTRUCTURE, BOTH PUBLIC AND PRIVATE, SHALL CONFORM WITH THE REQUIREMENTS OF THE GOVERNING MUNICIPALITY OR PUBLIC ENTITY WHERE APPLICABLE. NOTE THAT NOT ALL OF THE REQUIREMENTS ARE LISTED ON THESE PLANS AND/OR RELATED SPECIFICATIONS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT ALL APPLICABLE REQUIREMENTS ARE ADHERED TO.

**KEY NOTES**

- A. BUILDING A - RESIDENTIAL, HOTEL, RETAIL, RESTAURANT (12 STORIES PLUS ONE LEVEL OF UNDERGROUND PARKING).
- B. BUILDING B - RESTAURANT, OFFICE, RESIDENTIAL, RETAIL BUSINESS (12 STORIES)
- C. BUILDING C - PARKING GARAGE, RETAIL, RESIDENTIAL (7 STORIES)
- D. BUILDING D - RESIDENTIAL (6 STORIES)
- E. OUTDOOR SEATING AREA.
- F. LOADING AREA.
- G. AESTHETIC SIDEWALK TREATMENTS (TYP.).
- H. ALBERT AVENUE REALIGNED (2 LANES, 30' FACE-TO-FACE WITH BIKE LANES AND LEFT TURN LANE AT INTERSECTION).
- I. RETAINING WALL/ DECORATIVE SCREEN WALL (TYP.).
- J. ABBOT ROAD/GRAND RIVER IMPROVEMENTS. INCREASE WIDTH FROM 4 TO 6 LANES, ADDED DEDICATED LANES FOR TURNING AND THROUGH TRAFFIC.
- K. PEOPLE'S CHURCH DROP-OFF IMPROVEMENTS.
- L. GRAND RIVER SIDEWALK IMPROVEMENTS.
- M. EVERGREEN AVENUE REALIGNED (2 LANES, 30' FACE-TO-FACE WITH BIKE LANES).
- N. PUBLIC ALLEY IMPROVEMENTS.
- O. CONNECTING SKYWALK.

**Park District**

EAST LANSING, MI 48823



2502 Lake Lansing Rd.  
Ste C, Lansing,  
MI 48912



1427 West Saginaw Street, Suite 200  
East Lansing, Michigan 48823

office: 517.272.9835  
fax: 517.272.9836

www.bergmannpc.com

REVISIONS				
NO.	DATE	DESCRIPTION	REV.	CK'D

**OVERALL SITE PLAN**



**Know what's below.  
Call before you dig.**

NOT APPROVED:  
THIS PLAN HAS NOT RECEIVED FINAL APPROVAL OF ALL REVIEWING AGENCIES. THIS PLAN IS SUBJECT TO REVISIONS UNTIL ALL APPROVALS ARE OBTAINED AND SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES.

Project Manager:  
**T. AREND**  
Designed by:  
**P. FURTAW/A. NODARSE**  
Drawn by:  
**A. NODARSE**  
Checked by:  
**P. FURTAW**  
Date Issued:  
February 28, 2014  
Scale:  
**1" = 40'**

Project Number:  
**9843.000**  
File Name:  
**C100.DWG**

Drawing Number:

**C100**

DATE PLOTTED: 02/28/2014 10:05 AM / PROJECT: PARK DISTRICT PHASE 1A - EVERGREEN AVENUE REALIGNMENT / DRAWING: OVERALL SITE PLAN / SCALE: 1" = 40' / PLOTTER: HP DesignJet T1100