

BENCHMARKS:



- Benchmark #1: Big arm of fire hydrant on North side of Valley Court across from #248 West Grand River Avenue (car wash).
Elevation: 846.65
- Benchmark #2: Big arm of fire hydrant on North side of intersection of Evergreen Avenue and Albert Avenue.
Elevation: 853.44

GRADING NOTES

- REFER TO EROSION AND SEDIMENT CONTROL PLAN FOR REQUIRED EROSION AND SEDIMENT CONTROL MEASURES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REMOVAL OF TEMPORARY SEDIMENTATION CONTROLS. EROSION CONTROL MEASURES SHALL NOT BE REMOVED BEFORE VEGETATION HAS OCCURRED COMPLETELY.
- ALL SILT FENCE TO BE REPLACED WHENEVER THEY BECOME CLOGGED OR INOPERABLE AND SHALL BE REPLACED AT A MINIMUM OF EVERY 3 MONTHS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF TOPSOIL TO ALL DISTURBED AREAS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN EROSION CONTROL MEASURES AT ALL TIMES.
- SILT FENCE, JUTE MESH, AND/OR EROSION CONTROL BLANKETS WILL BE USED ON STEEP SLOPES AND WHEREVER NECESSARY TO CONTROL EROSION AND SILTATION OF EXISTING DRAINAGE SYSTEMS AS ORDERED BY THE ENGINEER OR SPECIFIED ON PLANS.
- THE CONTRACTOR SHALL DESIGNATE A MEMBER OF HIS/HER FIRM TO BE RESPONSIBLE TO MONITOR EROSION CONTROL, EROSION CONTROL STRUCTURES, TREE PROTECTION AND PRESERVATION THROUGHOUT CONSTRUCTION.
- ALL DISTURBED AREAS SHALL BE PROTECTED FROM EROSION EITHER BY MULCH OR TEMPORARY SEEDING WITHIN 2 WEEKS OF DISTURBANCE.
- ALL SITE GRADING MUST BE PERFORMED TO INSURE POSITIVE DRAINAGE ACROSS THE ENTIRE SITE, THROUGHOUT THE PERIOD OF CONSTRUCTION AND AFTER PROJECT COMPLETION.
- ALL SEDIMENTATION AND SOIL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF SITE GRADING AND MUST CONFORM TO PART 91 OF ACT 451 OF THE PUBLIC ACTS OF 1994 AS AMENDED. ALL APPLICABLE PERMITS SHALL BE OBTAINED BEFORE IMPLEMENTING THESE MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE SEDIMENTATION AND SOIL EROSION CONTROL MEASURES THROUGHOUT CONSTRUCTION.
- IN GENERAL, EARTHWORK AND PAVEMENT CONSTRUCTION SHOULD BE PERFORMED IN ACCORDANCE WITH THE LATEST MOST STANDARD SPECIFICATIONS FOR CONSTRUCTION UNLESS OTHERWISE NOTED.
- REMOVE ANY EXISTING TOPSOIL, ORGANIC SOILS, UNSUITABLE FILL, VEGETATION, TREES OR OTHER DELETERIOUS MATERIALS TO EXPOSE THE SUBGRADE SOIL, TREE ROOTS SHOULD BE COMPLETELY REMOVED.
- EXCAVATE TO THE DEPTH OF THE FINAL SUBGRADE ELEVATION TO ALLOW FOR GRADE CHANGES AND THE PLACEMENT OF THE RECOMMENDED PAVEMENT SYSTEM.
- ON SITE FILL MATERIAL CAN BE USED IF THE SPECIFIED COMPACTION REQUIREMENTS CAN BE ACHIEVED. IF ON SITE MATERIAL IS USED, IT SHOULD BE CLEAN AND FREE OF FROZEN SOIL, ORGANICS, OR OTHER DELETERIOUS MATERIALS.
- THE FINAL SUBGRADE SHOULD BE THOROUGHLY PROOFROLLED USING A LOADED TANDEM AXLE TRUCK UNDER THE OBSERVATION OF GEOTECHNICAL/PAVEMENT ENGINEER. LOOSE OR YIELDING AREAS THAT CANNOT BE MECHANICALLY STABILIZED SHOULD BE REMOVED AND REPLACED WITH ENGINEERED FILL OR AS DICTATED BY FIELD CONDITIONS.
- THE AGGREGATE BASE SHOULD BE COMPACTED TO ACHIEVE A MINIMUM OF 95 PERCENT OF THE MAXIMUM MODIFIED PROCTOR DRY DENSITY. THE BASE AND SUBGRADE COMPACTION SHOULD EXTEND A MINIMUM OF 12 INCHES BEYOND THE PAVED EDGE OR BACK OF CURB.

LEGEND

- 75 PROPOSED MAJOR CONTOUR
- 76 PROPOSED MINOR CONTOUR
- TC=78.01 BC=77.51 PROPOSED TOP OF CURB / BOTTOM OF CURB ELEVATION
- TC/TW=152.50 PROPOSED TOP OF CURB / TOP OF WALL
- 77.73 PROPOSED SPOT ELEVATION
- HP=77.73 PROPOSED HIGH POINT ELEVATION
- RE=77.73 PROPOSED RIM ELEVATION
- FF=77.73 FINISHED FLOOR ELEVATION
- 2.5% PROPOSED SLOPE
- 72 EXISTING CONTOUR
- EXISTING TOP OF CURB / BOTTOM OF CURB ELEVATION
- EXISTING SPOT ELEVATION
- EXISTING FLOOR ELEVATION
- RIDGE LINE



**Know what's below.
Call before you dig.**

NOT APPROVED:
THIS PLAN HAS NOT RECEIVED FINAL APPROVAL OF ALL REVIEWING AGENCIES. THIS PLAN IS SUBJECT TO REVISIONS UNTIL ALL APPROVALS ARE OBTAINED AND SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES.

Park District

EAST LANSING, MI 48823



2502 Lake Lansing Rd.
Ste C, Lansing,
MI 48912

Bergmann
associates
architects // engineers // planners

1427 West Saginaw Street, Suite 200
East Lansing, Michigan 48823

office: 517.272.9835
fax: 517.272.9836

www.bergmannpc.com

REVISIONS

NO.	DATE	DESCRIPTION	REV.	CK'D

**PRELIMINARY
GRADING PLAN**

Project Manager:
T. AREND
Designed by:
P. FURTAW / A. NODARSE
Drawn by:
A. NODARSE
Checked by:
P. FURTAW
Date Issued:
February 28, 2014
Scale:
1" = 40'

Project Number:
9843.00
File Name:
C120.DWG

Drawing Number:

C120

CIVIL ENGINEER: P. FURTAW, LICENSE NO. 94001, STATE OF MICHIGAN
 PROJECT: PARK DISTRICT PRELIMINARY GRADING PLAN
 DATE: FEBRUARY 28, 2014
 DRAWN BY: A. NODARSE
 CHECKED BY: P. FURTAW
 SCALE: 1" = 40'
 PROJECT NO: 9843.00